

Mildura and Irymple Stormwater Drainage Basins

Project Report

Mildura Rural City Council

Reference: 250641/354

Revision: 2

22 December 2017

Document control record

Document prepared by:

Aurecon Australasia Pty Ltd

ABN 54 005 139 873

Aurecon Centre

Level 8, 850 Collins Street

Docklands, Melbourne VIC 3008

PO Box 23061

Docklands VIC 8012

Australia

T +61 3 9975 3000

F +61 3 9975 3444

E melbourne@aurecongroup.com

W aurecongroup.com

A person using Aurecon documents or data accepts the risk of:

- a) Using the documents or data in electronic form without requesting and checking them for accuracy against the original hard copy version.
- b) Using the documents or data for any purpose not agreed to in writing by Aurecon.

Document control							aurecon
Report title		Project Report					
Document ID			Project number		250641/354		
File path							
Client		Mildura Rural City Council					
Client contact			Client reference				
Rev	Date	Revision details/status	Author	Reviewer	Verifier (if required)	Approver	
0	5 September 2017	Draft Report	AM	-	-	-	
1	17 October 2017	Updated Report	BR				
2	22 December 2017	Final Report	AS	BR	BR	BR	
Current revision		2					

Approval			
Author signature		Approver signature	
Name		Name	
Title		Title	

Contents

1	Introduction.....	4
2	Inputs and Assumptions	5
2.1	Infoworks Model Data	5
2.1.1	Rainfall Runoff Modelling.....	5
2.2	Drains Model Data	5
3	Stormwater Drainage Basins	7

Appendices

Appendix A Drawing Locality Plan

Appendix B Drawings Site Layout Plans

1 Introduction

Aurecon has been engaged by Mildura Rural City Council (MRCC) to assess the stormwater drainage basins required to service the new development areas within Irymple and Mildura South for the purpose of assisting with land acquisitions

The area and depths of the basins are established from the hydraulic modelling previously undertaken for these development areas.

The preliminary basin designs have been based on Lidar information provided by MRCC. The final basin configurations will be subject to further survey information and detailed design.

2 Inputs and Assumptions

The following models have been used to extract the information regarding the stormwater drainage basin volumes, depths and inlets and outlets

- Mildura South Model – Infoworks Modelling undertaken in 2013
- Irymple Drainage Model – Infoworks Modelling undertaken in 2013
- Benetook Avenue and Etiwanda Avenue – Drains Modelling undertaken in 2014

2.1 Infoworks Model Data

2.1.1 Rainfall Runoff Modelling

The fixed runoff model was used for runoff from impervious surfaces with a runoff coefficient of 1.0. The Horton infiltration model and SWMM routing model was used for modelling runoff from pervious areas with the following parameters:

- Soil type 3 (moderate runoff potential)
- Initial Infiltration rate = 250 mm/hr
- Ultimate Infiltration = 25.4 mm/hr
- Initial loss = 0.02m
- Runoff routing value (Manning's coefficient) for pervious areas = 0.2
- Runoff routing value (Manning's coefficient) for impervious areas = 0.012

Design storm events were developed for events with an Average Recurrence Interval (ARI) of 10, 20 and 100 years for durations varying from 0.5 hour to 72 hours, based on rainfall data derived in accordance with Australian Rainfall and Runoff guidelines

2.2 Drains Model Data

An ILSAX type hydrological model was developed for determining the rainfall runoff. The following parameters were input into the model:

- Soil type 2 (moderate infiltration potential)
- Paved (impervious) area depression storage = 2 mm
- Supplementary Area (not connected to the stormwater directly) depression storage = 5 mm
- Grassed (pervious) area depression storage = 10 mm
- Design storm events were developed for events with an ARI of 100 years, for durations ranging from 0.5 hour to 72 hours. The intensity patterns of the storms were based on Australian Rainfall and Runoff.

The design storms assessed include:

ARI	Storm Duration	Intensity
10 year	10 minute	78 mm/hr
	20 minute	55 mm/hr
	30 minute	43.8 mm/hr
	45 minute	34.4 mm/hr
	1 hour	34.4 mm/hr
	2 hours	17.5 mm/hr
	3 hour	13 mm/hr
	6 hour	7.8 mm/hr
	12 hour	4.69 mm/hr

ARI	Storm Duration	Intensity
100 year	10 minute	128.33 mm/hr
	20 minute	90 mm/hr
	30 minute	72 mm/hr
	45 minute	56 mm/hr
	1 hour	46.8 mm/hr
	2 hours	28.6 mm/hr
	3 hour	21.3 mm/hr
	6 hour	12.8 mm/hr

3 Stormwater Drainage Basins

The stormwater drainage basin layouts were modelled in Civil 3d to confirm area and depth required to achieve the necessary storage volume based on a 300mm freeboard. The 3d modelling is based on using Light Detection and Ranging (LIDAR) information provided by MRCC. It is recommended that detailed survey should be undertaken to confirm the basin levels.

Following stormwater drainage basins sites have been identified:

1. Deakin Basin – North West
2. Deakin Basin – South East
3. Etiwanda Basin
4. Delights Basin
5. Plane Tree basin
6. Calder Basin
7. Irymple Basin – South East
8. Irymple Basin – North West
9. Sandilong Basin – South East
10. Sandilong Basin – North West
11. Henderson Basin

Appendix A provides drawings showing the locality plan for all the above stormwater drainage basins.

The following table summarises the area requirement for each of the above stormwater drainage basins. A site layout drawing for each basin is provided at Appendix B along with detailed design drawings for the basin and connecting pipe system for those sites where detailed designs have been previously prepared for Council.

Mildura and Irymple Stormwater Drainage Basins Summary Table


Stormwater Drainage Basin	Storage Volume (m ³)	Area (m ²)	Average Depth (m)	Inlet Pipe Diameter (mm)	Outlet Pipe Diameter (mm)	Inlet Pipe Invert Level (m)	Outlet Pipe Invert Level (m)
Deakin Basin – North West	28,000	21,650	2.5	2,100	1,050	40.800	41.000
Deakin Basin – South East	61,866	44,602	1.9	N/A (surcharge pipe)	1,050	N/A (surcharge pipe)	xxx
Etiwanda Basin	315,350	203,152	2.18	N/A	1,350	N/A	41.900
Delights Basin	32,325	7,500	3.7	2 x 1350	900	43.800	42.60
Plane Tree Basin	4,997	9,210	1.75	600	375	48.450 49.500	49.500
Calder Basin	111,500	41,613	3.85	1,650	Rising main	42.80	N/A
Irymple Basin – South East	41,520	46,765	1.92	TBC	900	TBC	42.500
Irymple Basin – North West	15,800	8,800	1.8	900,450 & 300	900	41.7	41.7
Sandilong Basin – South East	15,000	10,500	1.43	2x900	675	43.527	43.194
Sandilong Basin – North West	6,000	4,283	1.4	1200	525	46.474	46.20
Henderson Basin	30,305	14,932	3.5	2,250	1,200	42.280	42.280



A

DRAWING
LOCALITY PLAN

Plot Date: 17/10/2017 11:55:39 AM Filename: P:\250641 MRCC\250641-354 MILDURA SOUTH DCP DRAINAGE ASSESSMENT\3 PROJECT DELIVERY\CADD\DRAWINGS\CIV\250641-354-DRG-LOCATIONS.DWG



CLIENT		REV	DATE	REVISION DETAILS	APPROVED	SCALE	SIZE	PRELIMINARY NOT FOR CONSTRUCTION	PROJECT	MILDURA AND IRYMPLE STORMWATER DRAINAGE BASIN						
 Mildura Rural City Council	A	17.10.17	PRELIMINARY ISSUE		B.RIELLEY	NTS	A3		APPROVED	TITLE	BASIN LOCATIONS					
									DATE							
					</											



B

DRAWINGS
SITE LAYOUT PLAN



Deakin Basin
- North West

Plot Date: 18/02/21 12:15:02 PM Office: AUMOL Filename: P:250641_MROCC250641_354_MILDURA_SOUTH_DCP_DRAINAGE_ASSESSMENT\PROJECT DELIVERY\DRAWINGS\DWG\250641_354_DRG-200.DWG



LEGEND

- PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- EXISTING PROPERTY PARCEL
- WATER EDGE
- Ex SW
- Ex SW
- EXISTING STORM WATER
- FUTURE SW
- FUTURE STORMWATER

DEAKIN BASIN - NW

STORAGE VOLUME	28000m3
AREA	21650m2
AVERAGE DEPTH	2.5m
INLET PIPE (P1)	21000
INLET INVERT	40.800
OUTLET PIPE (P2)	10500
OUTLET INVERT	41.000

PLAN
1:1000

CLIENT

REV	DATE	REVISION DETAILS	APPROVED
A	14.09.16	PRELIMINARY ISSUE	

SCALE	SIZE
AS SHOWN	A1
DRAWN	C.TOTENHOFER
DESIGNED	H.SINGH
CHECKED	

PRELIMINARY NOT FOR CONSTRUCTION
APPROVED
DATE

PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESMENT
TITLE	DEAKIN BASIN - NORTH WEST
DRAWING No.	PROJECT No. 250641 - WBS 354 - TYPE DRG - DISC CC - NUMBER 200 - REV A



Deakin Basin
- South East



LEGEND	
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	EXISTING MAJOR CONTOUR
	EXISTING MINOR CONTOUR
	EXISTING PROPERTY PARCEL
	WATER EDGE
	SW
	EXISTING STORM WATER
	FUTURE STORMWATER

DEAKIN BASIN - SE	
STORAGE VOLUME	61866m3
AREA	44602m2
AVERAGE DEPTH	1.9m
INLET PIPE (P1)	2100 Ø
INLET INVERT	N/A SURCHARGE BASIN
OUTLET PIPE (P2)	2100 Ø
OUTLET INVERT	N/A SURCHARGE BASIN

PLAN
1:1000

Proj Date: 27/03/2017 10:06:15 AM, Office: AUMC, File Name: P:250641 MRC0250641 354 MILDURA SOUTH DCP DRAINAGE ASSESSMENT\PROJECT DELIVERY\CD\DRAWINGS\CD\250641 354\DRG-200 DEAKIN BASIN.DWG

REV	DATE	REVISION DETAILS	APPROVED
A	14.09.16	PRELIMINARY ISSUE	


SCALE	SIZE
AS SHOWN	A1
DRAWN C.TOTENHOFER	
DESIGNED H.SINGH	
CHECKED	

PRELIMINARY NOT FOR CONSTRUCTION	
APPROVED	DATE

PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESSMENT	
TITLE	DEAKIN AVE BASIN - SOUTH EAST	
DRAWING No.	PROJECT No. 250641	WBS 354
	TYPE DRG	DISC CC
	NUMBER 200	REV A



Etiwanda Basin



LEGEND	
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	EXISTING MAJOR CONTOUR
	EXISTING MINOR CONTOUR
	EXISTING PROPERTY PARCEL
	WATER EDGE
	EXISTING STORM WATER

ETIWANDA BASIN	
STORAGE VOLUME (WITH 0.150m FREEBOARD)	315350m3
FOOTPRINT AREA	203152m2
AVERAGE DEPTH	2.18m
INLET PIPE (P1)	1350Ø
INLET INVERT (P1)	N/A SURCHARGE BASIN
OUTLET PIPE (P1)	1350Ø
OUTLET INVERT (P1)	41.9

PLAN
1:1500

Proj Date: 27/10/2017 10:07:29 AM Client: AUMC File Name: P:250641 MRC0250641 354 MILDURA SOUTH DCP DRAINAGE ASSESSMENT\PROJECT DELIVERY\CDRAWINGS\CDU\250641 354\DRG-600 ETIWANDA BASIN.DWG

REV	DATE	REVISION DETAILS	APPROVED
A	07.12.16	PRELIMINARY ISSUE	

SCALE	SIZE
AS SHOWN	A1
DRAWN C.TOTENHOFER	
DESIGNED H.SINGH	
CHECKED	


PRELIMINARY NOT FOR CONSTRUCTION	
APPROVED	DATE

PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESMENT				
TITLE	ETIWANDA BASIN				
DRAWING No.	PROJECT No.	WBS	TYPE	DISC	NUMBER
250641	-	354	-	DRG	CC
					600
					REV
					A



Delights
Basin

Plot Date: 27/03/2017 11:40:09 AM File Name: P:\250641\PROJECTS\250641\DCP\DRAWINGS\250641-351\DCP-000 DELIGHTS BASIN.DWG



LEGEND	
	MAJOR DESIGN CONTOUR
	MINOR DESIGN CONTOUR
	EXTEND OF EXISTING ROCK BEACHING
	EXISTING FENCE
	PROPOSED 1.8m HIGH CYCLONE/WIRE MESH FENCE OR SIMILAR APPROVED
	PROPOSED 1.2m HIGH GALVANISED FENCE REFER TO DETAIL ON SHEET 004
	EXISTING STORMWATER
	EXISTING SEWER
	EXISTING IRRIGATION DRAINAGE
	EXISTING STORMWATER DRAINAGE TO BE DECOMMISSIONED
	PROPERTY BOUNDARY
	EXISTING STORMWATER PIPES
	AREA OF SEWER TO BE PROTECTED REFER TO DETAIL ON SHEET C06
	PROPOSED ROCK BEACHING
	EXISTING PITS
	PROPOSED HEAD WALL

DELIGHTS BASIN	
STORAGE VOLUME	32325m3
FOOTPRINT AREA	7500m2
AVERAGE DEPTH	3.7m
EXISTING INLET PIPE	2 x 13500
EXISTING INLET INVERT	43.800
PROPOSED OUTLET PIPE	9000
PROPOSED OUTLET INVERT	42.6




WARNING AND DISCLAIMER BEWARE OF UNDERGROUND SERVICES

The information provided in these drawings relating to the positions of underground services is intended to be only a guide for excavation works. Aurecon does not warrant or represent that the positions of those services shown on the drawings are accurate. Furthermore, services may exist of which Aurecon is unaware. The information provided should therefore not be relied upon and exact positions of services should be verified by hand excavation. Furthermore, Aurecon disclaims responsibility for damage or injury to any person caused directly or indirectly by any works affecting the services.

Dated: April 16


REV	DATE	REVISION DETAILS	APPROVED	SCALE	SIZE	FOR CONSTRUCTION	PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESSMENT					
D	29.01.15	FOR COMMENT	-	1:250	A1	APPROVED DATE 07.04.16 Brett Rielley B. RIELLEY	TITLE	DELIGHTS BASIN					
T0	11.02.15	TENDER ISSUE	-										
T1	07.04.15	REVISED TENDER ISSUE	-	DRAWN C.TOTENHOFFER			DRAWING No.	PROJECT No. 250641	WBS 354	TYPE DRG	DISC CC	NUMBER 900	REV 1
T2	15.12.15	REVISED TENDER ISSUE	-	DESIGNED M.MCCRANN									
T3	04.02.16	REVISED TENDER ISSUE	B.RIELLEY	CHECKED P.DePALMA									
0	19.04.16	CONSTRUCTION ISSUE	B.RIELLEY										
T4	30.11.16	TENDER ISSUE	B.RIELLEY										
1	12.05.17	ISSUE FOR CONSTRUCTION	B.RIELLEY										




Mildura Rural City Council

ETIWANDA SPURLINE DRAINAGE BASIN

LOCALITY PLAN



DRAWING REFERENCE PLAN



aurecon

www.aurecongroup.com

ABN: 54 005 139 873

A person using the Aurecon drawings and other data accepts the risk of using the drawings and other data:
1. In electronic form without requesting and checking them for accuracy against the original hard copy versions;
2. For any purposes not agreed to in writing by Aurecon.
Wherever a discrepancy in the contract documents is found and unless directed otherwise by the Principal/Engineer, the contractor shall adopt, at their own cost the greater quantum, class of finish, grade, or specification where applicable.

FOR CONSTRUCTION

SIZE	DATE	DRAWING No.	PROJECT No.	WBS	TYPE	DISC	NUMBER	REV
A1	11.05.17		242814	325	DRG	CC	000	1

1. THE CONTRACTOR SHALL CHECK ALL SERVICE LOCATIONS PRIOR TO COMMENCING WORK.
2. PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ON THE SITE THE CONTRACTOR SHALL CONTACT THE RELEVANT AUTHORITIES TO ASCERTAIN THE POSSIBLE LOCATION OF FURTHER SERVICES AND DETAILED LOCATION AND DEPTH OF ALL SERVICES AND ARRANGE FOR THEIR RELOCATION WHERE NECESSARY.
3. THE DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE SPECIFICATIONS ISSUED BY THE SUPERINTENDENT AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT.
4. ALL LEVELS ARE EXPRESSED IN METRES ABOVE AUSTRALIAN HEIGHT DATUM (AHD).
5. GRID COORDINATES ARE TO MAP GRID OF AUSTRALIA, ALL NORTH POINTS INDICATE TRUE NORTH.
6. THE DRAWINGS SHALL NOT BE SCALED.
7. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE (U.N.O.).
8. ALL RADII ARE EXPRESSED IN METERS (U.N.O.).
9. THE LOCATIONS OF ALL EXISTING SURFACE PITS, VALVE COVERS, ETC. SHOWN ON DRAWINGS HAVE BEEN REPRODUCED FROM SURVEY SUPPLIED BY AURECON AUSTRALIA, THE LOCATIONS OF UNDERGROUND SERVICES HAVE BEEN NOTED FROM EXISTING RECORDS, AS VARIATIONS WITH RECORDS MAY EXIST COMPLETE ACCURACY CANNOT BE GUARANTEED, ALL EXISTING SERVICES LOCATIONS SHALL BE VERIFIED ON SITE BY THE CONTRACTOR BEFORE COMMENCING WORK.
10. THE CONTRACTOR SHALL TRANSFER TBM'S OUT OF THE CONSTRUCTION AREA PRIOR TO COMMENCEMENT OF EXCAVATION WORKS.
11. REFER TO PIT SCHEDULE FOR ALL PIT DETAILS.
12. CARE SHALL BE TAKEN WHEN EXCAVATING IN THE VICINITY OF SERVICES.
13. EXCAVATION WITHIN 4.5m RADIUS OF TREES SHALL BE CARRIED OUT WITH HAND HELD EQUIPMENT. CUTTING OF TREE ROOTS GREATER THAN 25mm DIA SHALL BE CARRIED OUT UNDER THE SUPERVISION OF AN ARBORIST.
14. THE CONTRACTOR SHALL MAINTAIN ALL WORK SITES IN A SAFE STABLE, AND TRAFFICABLE CONDITION.
15. THE CONTRACTOR SHALL ERECT AND MAINTAIN ALL SHORING, PLANKING, AND STRUTTING, DEWATERING DEVICES, BARRICADES, SIGNS, LIGHTS, ETC NECESSARY TO KEEP WORKS IN A SAFE AND STABLE CONDITION AND FOR THE PROTECTION OF THE PUBLIC.
16. DISPOSAL OF EXCESS SPOIL: TRUCK ROUTE AND DISPOSAL LOCATION SHALL BE SUBMITTED TO THE SUPERINTENDENT FOR APPROVAL.
17. SEWERS DRAINING FLOOR OF BASINS TO BE EXCAVATED TO WITHIN 100mm OF TOP OF PIPE. EXISTING EMBEDMENT GRAVEL TO BE LEVELLED AND OVERLAYED WITH A34 B10M GEOTEXTILE. TRENCH SHALL BE BACKFILLED WITH MATERIAL THAT MEETS ALL REQUIREMENTS OF CLAY LINER GRADE MATERIAL TO MINIMUM DEPTH OF 900mm.
18. THE CONTRACTOR SHALL ENSURE THAT NO POLLUTED OR SEDIMENT LADEN RUNOFF ENTERS ANY DRAIN OR WATERCOURSE. THE CONTRACTOR SHALL ENSURE THAT PRECAUTIONS ARE TAKEN TO PREVENT EMISSION OF DUST, WHETHER FROM THE OPERATION OF CONSTRUCTION EQUIPMENT OR OTHERWISE.
19. THE CONTRACTOR SHALL ADJUST ALL AFFECTED SERVICE COVERS TO MATCH NEW PAVEMENT LEVELS AS APPROVED BY THE SUPERINTENDENT AND STATUTORY AUTHORITIES.
20. WHERE OPTIC FIBRE EXISTS THE CONTRACTOR SHALL COORDINATE EXCAVATION WORKS WITH TELSTRA.
21. THE CONTRACTOR SHALL UNDERTAKE WORKS IN ACCORDANCE WITH THE RELEVANT CONFINED SPACE STANDARDS AND REGULATIONS WHERE APPROPRIATE.
22. THE CONTRACTOR SHALL TAKE EXTREME CAUTION WHEN EXCAVATING NEAR EXISTING BUILDING FOOTINGS.
23. CONTRACTOR TO ADVISE SUPERINTENDENT OF ASSOCIATED WORK PROGRAMME.
24. ALL DIMENSIONS RELEVANT TO SET OUT SHALL BE CONFIRMED AND VERIFIED BY THE CONTRACTOR BEFORE CONSTRUCTION IS COMMENCED. THE CONTRACTOR SHALL REPORT ANY DISCREPANCIES TO THE SUPERINTENDENT.
25. WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE RELEVANT CURRENT SAA AND VICROADS STANDARDS PLUS LOCAL STATUTORY AUTHORITIES REQUIREMENTS EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
26. WHERE WORKS ARE IN THE VICINITY OF EXISTING SERVICES, THESE SERVICES SHALL BE LOCATED AND EXPOSED/PROVED PRIOR TO COMMENCEMENT OF WORKS AND THE RELEVANT AUTHORITIES NOTIFIED SEVEN (7) CLEAR DAYS PRIOR TO THE COMMENCEMENT OF THE WORKS. ANY CLASHES BETWEEN EXISTING ASSETS AND PROPOSED WORKS ARE TO BE REPORTED TO THE SUPERINTENDENT IMMEDIATELY. SERVICE AUTHORITIES' REQUIREMENTS FOR WORKS WITHIN THE VICINITY OF THEIR ASSETS ARE TO BE FOLLOWED AND RELEVANT PERMITS OBTAINED AT THE CONTRACTOR'S EXPENSE.
27. PRIOR TO THE COMMENCEMENT OF THE WORKS, THE CONTRACTOR SHALL PROVIDE THE FOLLOWING INFORMATION:
 - (A) SOURCE OF QUARRY MATERIAL
 - (B) OPTIMUM MOISTURE CONTENT AND MAXIMUM DRY DENSITY OF THE FINE CRUSHED ROCK TO BE USED (FROM NATIONAL ASSOCIATION OF TESTING AUTHORITIES)
 - (C) IF THE SOURCE OF THE QUARRY MATERIAL IS CHANGED DURING THE COURSE OF THE WORKS
28. ALL REDUNDANT ASSETS SHALL BE REMOVED AND DISPOSED OF OFF SITE WITH THE PERMISSION OF THE ASSETS' OWNER.
29. ALL TRENCHES TO BE BACKFILLED AS PER RELEVANT STANDARD MRCC DRAWING 010-1013 AND VICROADS STANDARD DRAWING SD-1511
30. PROPOSED RCP'S TO BE INSTALLED IN ACCORDANCE WITH RELEVANT VICROADS STANDARD DRAWINGS AND SPECIFICATIONS IN VICROADS ROADS AND IN ACCORDANCE WITH RELEVANT MRCC STANDARD DRAWINGS AND SPECIFICATIONS IN MRCC ROADS.
31. PRIOR TO COMMENCEMENT OF WORKS THE CONTRACTOR IS TO LOCATE ALL EXISTING TELSTRA SERVICES WITHIN THE VICINITY OF THE PROPOSED WORKS. THE CONTRACTOR IS TO LIAISE WITH TELSTRA AND FOLLOW ALL THEIR REQUIREMENTS WHEN WORKING IN THE VICINITY OF THEIR ASSETS. PROTECTION OR RELOCATION OF TELSTRA ASSETS TO FACILITATE THE CONSTRUCTION OF THIS PROJECT IS TO BE CONDUCTED IN ACCORDANCE WITH TELSTRA REQUIREMENTS AND AT THE CONTRACTOR'S EXPENSE. ALL RELEVANT PERMITS ARE TO BE OBTAINED AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR IS TO TAKE APPROPRIATE SAFETY MEASURES AND FOLLOW ALL LEGISLATIVE AND TELSTRA REQUIREMENTS WHEN WORKING IN THE VICINITY OF EXISTING ASBESTOS CEMENT SERVICES.

OH1.	THE CONTRACTOR SHALL CHECK FOR CONTAMINANTS PRIOR TO ENTERING DRAINAGE SYSTEM.
OH2.	THE CONTRACTOR SHALL INTRODUCE MANUAL HANDLING PROCEDURES PRIOR TO CONSTRUCTION AND MAINTENANCE WORKS.
OH3.	THE CONTRACTOR SHALL INTRODUCE SAFE MAINTENANCE PROCEDURES PRIOR TO UNDERTAKING MAINTENANCE WORKS ON THE ASSETS.
OH4.	THE CONTRACTOR SHALL UNDERTAKE WORKS IN ACCORDANCE WITH THE RELEVANT CONFINED SPACE STANDARDS AND REGULATIONS WHERE APPROPRIATE.
OH5.	CONTRACTOR SHOULD EXERCISE EXTREME CARE WHEN WORKING IN THE VICINITY OF UNDERGROUND AND OVERHEAD POWER INFRASTRUCTURE IN ACCORDANCE WITH RELEVANT LEGISLATIVE REQUIREMENTS.
OH6.	PRIOR TO COMMENCEMENT OF WORKS ON SITE THE CONTRACTOR SHALL ENSURE THAT ALL MATTERS RELATING TO THE OCCUPATIONAL HEALTH AND SAFETY HAVE BEEN COMPLIED WITH.
OH7.	AT THE COMPLETION OF THE WORKS, ALL RUBBISH, DEBRIS AND SURPLUS MATERIALS SHALL BE REMOVED AND THE SITE SHALL BE CLEARED TO THE SATISFACTION OF THE SUPERINTENDENT.
OH8.	CONTRACTOR SHALL PROVIDE FENCING TO ALL OPEN EXCAVATION.
OH9.	ALL EXCAVATIONS DEEPER THAN 1.5m SHALL BE SHORED IN ACCORDANCE WITH OHS REQUIREMENTS AND LEGISLATION.
OH10.	IT IS NOT GUARANTEED THAT ALL SERVICES HAVE BEEN SHOWN ON THE DRAWINGS, CONTRACTOR TO UNDERTAKE A DBYD BEFORE THE COMMENCEMENT OF WORKS
OH11.	MAKE ALL NECESSARY REPAIRS TO EXISTING SERVICES AND INFRASTRUCTURE TO AN 'AS GOOD AS NEW' CONDITION AT THE CONTRACTOR'S EXPENSE.
OH12.	THESE DRAWINGS ARE A SCHEMATIC REPRESENTATION OF SERVICES INFORMATION CONTAINED IN DRAWINGS ISSUED BY THE RELEVANT AUTHORITIES. THE INFORMATION CONTAINED IN THESE DRAWINGS IS INDICATIVE ONLY, AND REFERENCE SHOULD BE MADE TO THE RELEVANT AUTHORITIES DOCUMENTATION TO CONFIRM ACCURACY AND COMPLETENESS. WHERE INFORMATION IS AVAILABLE, THE SUB-SURFACE SERVICES INSTALLED BY CONTRACTORS OTHER THAN THE AUTHORITIES HAVE BEEN SHOWN, BUT ADDITIONAL UNDOCUMENTED SERVICES MAY BE PRESENT. SHOULD THE CONTRACTOR BELIEVE THAT SUB-SURFACE SERVICES ARE AT RISK OF DAMAGE DURING CONSTRUCTION, THE CONTRACTOR SHOULD NOTIFY THE RELEVANT AUTHORITIES AND ESTABLISH THE EXACT LOCATION OF THE SERVICES.

CS1.	EXCAVATED MATERIAL MUST BE ASSESSED FOR CONTAMINATION AND MANAGED ACCORDING TO THE INDUSTRIAL WASTE RESOURCE GUIDELINES IWRG621 FROM THE EPA.
CS2.	CONTAMINATED SOIL LOW LEVEL AS DESCRIBED BY THE EPA PUBLICATION 448 CAN BE DISPOSED OF AT THE MILDURA LANDFILL LOCATED ON ONTARIO AVENUE, FOLLOWING THE EPA WASTE DISCHARGE LICENCE NO HS1302. HIGHER CONTAMINATED SOILS MUST BE TREATED OR STABILISED AS REQUIRED BY THE EPA.
CS3.	CONTAMINATED SOIL CONTAINING ASBESTOS CAN ALSO BE DISPOSED OF AT THE MILDURA LANDFILL FOLLOWING EPA WASTE DISCHARGE LICENCE NO HS1302 AND THE CORRESPONDING HEALTH AND SAFETY CONSIDERATIONS.
CS4.	VEHICLES SHALL USE A WHEEL CLEANING FACILITY TO PREVENT CONTAMINATED MATERIALS LEAVING THE SITE.
CS5.	CONTAMINATED MATERIALS SHOULD BE COVERED BY APPROVED MATERIAL AFTER DEPOSITION.
CS6.	CONTRACTOR TO FOLLOW BEST PRACTICE ENVIRONMENTAL MANAGEMENT SITING, DESIGN, OPERATION AND REHABILITATION OF LANDFILLS, EPA PUBLICATION 788.1, SEPTEMBER 2010 WHEN DISPOSING MATERIALS IN THE LANDFILL.

A1. ALL ASBESTOS WHICH REQUIRES REMOVAL OR DISTURBANCE AS PART OF THE CONSTRUCTION WORKS SHALL BE REMOVED BY AN ACCREDITED ASBESTOS REMOVALIST REGISTERED WITH THE OCCUPATIONAL HEALTH AND SAFETY AUTHORITIES.

A2. EXISTING CONSTRUCTION MAY CONTAIN ASBESTOS CONTAMINATED PRODUCTS. MATERIALS THOUGHT TO CONTAIN ASBESTOS MUST BE INSPECTED BY A CERTIFIED INSPECTOR CAPABLE OF SAMPLING FOR THE EXISTENCE OF ASBESTOS. WORKS SHALL BE DONE IN ACCORDANCE WITH THE MOST CURRENT WORKSAFE REGULATIONS AND DISPOSED OF IN ACCORDANCE WITH CURRENT REGULATIONS.


T1 THE DOCUMENTED DESIGN IS FOR THE PERMANENT CONDITION ONLY AND DOES NOT SPECIFICALLY CATER FOR THE INTERIM ARRANGEMENTS DURING CONSTRUCTION AND ERECTION UNLESS NOTED OTHERWISE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURE AND ANY ADJACENT STRUCTURES IN A SAFE AND STABLE CONDITION AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR IS TO ENGAGE A QUALIFIED AND SUITABLY EXPERIENCED ERECTING ENGINEER TO REVIEW AND APPROVE THE CONTRACTORS CONSTRUCTION METHODOLOGY AND TO PROVIDE THE DESIGN OF ANY TEMPORARY WORKS (SUCH AS PROPPING AND TEMPORARY BRACING) TO SUIT THE CONTRACTORS CONSTRUCTION SEQUENCE AND METHODOLOGY.

THE CONTRACTOR SHALL SUBMIT DESIGN CALCULATIONS AND DRAWINGS TO THE SUPERINTENDENT UPON REQUEST AS EVIDENCE THAT A SAFE ERECTING METHODOLOGY HAS BEEN PUT FORWARD.

DRAWING INDEX			
DRAWING NUMBER	DRAWING TITLE	REVISION	DATE
242814-325-DRG-CC-000	COVER SHEET	1	11.05.17
242814-325-DRG-CC-001	GENERAL NOTES AND DRAWING INDEX	1	11.05.17
242814-325-DRG-CC-002	BASIN LAYOUT	1	11.05.17
242814-325-DRG-CC-003	BASIN SECTIONS	1	11.05.17
242814-325-DRG-CC-004	BASIN DETAILS	1	11.05.17

NOTE: BEFORE COMMENCEMENT OF WORK, CONTRACTOR IS TO EXPOSE ALL EXISTING SERVICES AND PROVIDE REPORT TO SUPERINTENDENT REPORTING ALL CLASHES



Mildura Rural City Council

[illegible]

Rev Date: 12/20/17 3:11:54 PM Office: ALMOJ File Name: P:242814 - HRC242814-325 ETIWANDA SPURLINE CAD/DRG/SCV/242814-325-DRG-CC-002 [BASIN.DWG]


CLIENT

REV	DATE	REVISION DETAILS	APPROVED
D	29.01.15	FOR COMMENT	-
T0	11.02.15	TENDER ISSUE	-
T1	07.04.15	REVISED TENDER ISSUE	-
T2	15.12.15	REVISED TENDER ISSUE	-
T3	04.02.16	REVISED TENDER ISSUE	B.RIELLEY
0	19.04.16	CONSTRUCTION ISSUE	B.RIELLEY
T4	30.11.16	TENDER ISSUE	B.RIELLEY
1	12.05.17	ISSUE FOR CONSTRUCTION	B.RIELLEY

SCALE	SIZE
1:250	A1
DRAWN	
C.TOTENHOFER	
DESIGNED	
M.MCCRANN	
CHECKED	
P.DePALMA	

FOR CONSTRUCTION
APPROVED
Brett Rielley
DATE 07.04.16
B.RIELLEY

PROJECT	ETIWANDA SPURLINE DRAINAGE BASIN DESIGN
TITLE	BASIN LAYOUT
DRAWING No.	PROJECT No. 242814 - WBS 325 - TYPE DRG - DISC CC - NUMBER 002 - REV 1



LEGEND


---	MAJOR DESIGN CONTOUR
---	MINOR DESIGN CONTOUR
---	EXTEND OF EXISTING ROCK BEACHING
---	EXISTING FENCE
---	PROPOSED 1.8m HIGH CYCLONE/WIRE MESH FENCE OR SIMILAR APPROVED
---	PROPOSED 1.2m HIGH GALVANISED FENCE REFER TO DETAIL ON SHEET 004
---	EXISTING STORMWATER
---	EXISTING SEWER
---	EXISTING IRRIGATION DRAINAGE
---	EXISTING STORMWATER DRAINAGE TO BE DECOMMISSIONED
---	PROPERTY BOUNDARY
---	EXISTING STORMWATER PIPES
---	AREA OF SEWER TO BE PROTECTED REFER TO DETAIL ON SHEET C06
---	PROPOSED ROCK BEACHING
---	EXISTING PITS
---	PROPOSED HEAD WALL




WARNING AND DISCLAIMER BEWARE OF UNDERGROUND SERVICES

The information provided in these drawings relating to the positions of underground services is intended to be only a guide for excavation works. Aurecon does not warrant or represent that the positions of those services shown on the drawings are accurate. Furthermore, services may exist of which Aurecon is unaware. The information provided should therefore not be relied upon and exact positions of services should be verified by hand excavation. Furthermore, Aurecon disclaims responsibility for damage or injury to any person caused directly or indirectly by any works affecting the services.

Dated: April 16


[illegible]

A-A LONG SECTION

[illegible]

B-B LONG SECTION

BENETOOK 14TH 15TH ETIWANDA BENETOOK CONTROL TABLE				
REFERENCE	EAST	NORTH	ELEVATION	DESCRIPTION
503	806693.998	6214202.178		TPEG
101	806066.044	6213418.214		TPEG
1031	806114.191	6213464.549		TPEG
1565	806050.331	6213262.973		TPEG
1568	806028.307	6213285.697		TPEG
PM357	806994.470	6213892.602	51.233	PSM
PM407	806668.008	6216219.236	51.629	PSM
PM746	805516.767	6211545.996	47.412	PSM
PM1094	807351.012	6211563.996	45.156	PSM
PM1103	806480.685	6212488.603	47.014	PSM
PM1104	806034.092	6212946.856	47.028	PSM





The information provided in these drawings relating to the positions of underground services is intended to be only a guide for excavation works. Aurecon does not warrant or represent that the positions of those services shown on the drawings are accurate. Furthermore, services may exist of which Aurecon is unaware. The information provided should therefore not be relied upon and exact positions of services should be verified by hand excavation. Furthermore, Aurecon disclaims responsibility for damage or injury to any person caused directly or indirectly by any works affecting the services.

Dated: April 16

REV	DATE	REVISION DETAILS	APPROVED	SCALE	SIZE	FOR CONSTRUCTION	PROJECT	ETIWANDA SPURLINE DRAINAGE BASIN									
D	29.01.15	FOR COMMENT	-	AS SHOWN	A1	APPROVED DATE 07.04.16 Brett Rielley B.RIELLEY	TITLE	BASIN SECTIONS									
T0	11.02.15	TENDER ISSUE	-														
T1	07.04.15	REVISED TENDER ISSUE	-	DRAWN													
T2	15.12.15	REVISED TENDER ISSUE	-	C.TOTENHOFFER													
T3	04.02.16	REVISED TENDER ISSUE	B.RIELLEY	DESIGNED													
0	19.04.16	CONSTRUCTION ISSUE	B.RIELLEY	M.MCCRANN													
T4	30.11.16	TENDER ISSUE	B.RIELLEY	CHECKED													
1	12.05.17	ISSUE FOR CONSTRUCTION	B.RIELLEY	P.DePALMA			DRAWING No.	PROJECT No.	WBS	TYPE	DISC	NUMBER	REV				
							242814	-	325	-	DRG	-	CC	-	003	-	1

Rev Date: 12/01/2017 3:11:38 PM Office: ALMO File Name: P:\202814 - HRC\202814-35 ETIWANDA SPURLINE\CAD\DRG\DWG\2814-35-DRG-CC-004-1111 BASIN.DWG




ROCK BEACHING AT W2-8-1

1:50

NOTE: RIP RAP PROTECTION TO BE IN ACCORDANCE WITH TABLE BELOW.


ROCK CLASS (SECTION THICKNESS)	ROCK SIZE (m)	ROCK MASS (kg)	MINIMUM % OF ROCK LARGER THAN:
FACING 0.5m	0.4	100	0
	0.3	35	50
	0.15	2.5	90

DETAIL 1
1:50 C02



TYPICAL EXISTING SEWER PROTECTION

1:50




ROCK BEACHING AT W2-7-1

1:50

NOTE: RIP RAP PROTECTION TO BE IN ACCORDANCE WITH TABLE BELOW.

ROCK CLASS (SECTION THICKNESS)	ROCK SIZE (m)	ROCK MASS (kg)	MINIMUM % OF ROCK LARGER THAN:
FACING 0.5m	0.4	100	0
	0.3	35	50
	0.15	2.5	90

DETAIL 2
1:50 C02






TYPICAL JUTEMAT DETAIL

1:20



TYPICAL HEADWALL FENCE

NTS




ROCK BEACHING AT N09

1:50

NOTE: RIP RAP PROTECTION TO BE IN ACCORDANCE WITH TABLE BELOW.

ROCK CLASS (SECTION THICKNESS)	ROCK SIZE (m)	ROCK MASS (kg)	MINIMUM % OF ROCK LARGER THAN:
FACING 0.5m	0.4	100	0
	0.3	35	50
	0.15	2.5	90

DETAIL 3
1:50 C02



REV	DATE	REVISION DETAILS	APPROVED
D	29.01.15	FOR COMMENT	
T0	11.02.15	TENDER ISSUE	
T1	07.04.15	REVISED TENDER ISSUE	
T2	15.12.15	REVISED TENDER ISSUE	
T3	04.02.16	REVISED TENDER ISSUE	B.RIELLEY
0	19.04.16	CONSTRUCTION ISSUE	B.RIELLEY
T4	30.11.16	TENDER ISSUE	B.RIELLEY
1	12.05.17	ISSUE FOR CONSTRUCTION	B.RIELLEY

SCALE	SIZE
AS SHOWN	A1
DRAWN	
C.TOTENHOFER	
DESIGNED	
M.MCCRANN	
CHECKED	
P.DePALMA	

FOR CONSTRUCTION
APPROVED
DATE 07.04.16
Brett Rielley
B.RIELLEY

PROJECT	ETIWANDA SPURLINE DRAINAGE BASIN DESIGN
TITLE	BASIN DETAILS
DRAWING No.	242814
PROJECT No.	242814
WBS	325
TYPE	DRG
DISC	CC
NUMBER	004
REV	1

Safe Design Risk Register – Etiwanda Spurline Basin Works

Client		Mildura Rural City Council			Workshop Date		-				Risk Rating Matrix	Likelihood of occurrence					
Stakeholders		MRCC / Service authorities / Contractor			Revision No.		1					Most Likely Consequence	5 - Very likely	4 - Good chance	3 - Likely	2 - Unlikely	1 - Very unlikely
Meeting Attendees		M. Pendlebury			Project No.				242814-325			A - Disastrous	Extreme	Extreme	Extreme	Extreme	High
					Project Leader				Andrew Seaton-Stewart			B - Critical	Extreme	Extreme	Extreme	High	High
		A.Seaton-Stewart			Project Director				Brett Rielley			C - Serious	Extreme	High	High	Moderate	Moderate
											D - Significant	High	High	Moderate	Low	Low	
											E - Minor	Moderate	Moderate	Low	Low	Low	


- | | | | | | | | |
|----|--|--|--|--|--|--|--|
| 1. | This risk register has been prepared to document hazards and risk treatments associated with project elements designed by Aurecon, including subconsultants where applicable. | | | | | | |
| 2. | The full life cycle of the project has been considered including design, construction (and commissioning), operation, maintenance, modification and demolition phases. | | | | | | |
| 3. | The risk register is focussed on hazards resulting from atypical features specific to the design. It is expected that risks associated with generic hazards (working at heights, excavations, etc) will be addressed by other stakeholders using appropriate risk management techniques during subsequent phases of the project. | | | | | | |
| 4. | Residual risks which cannot reasonably be actioned by Aurecon during the design phase have been identified and require action by other stakeholders during subsequent phases of the project (eg construction, operations, maintenance, modification or demolition). | | | | | | |
| 5. | This risk register does not replace the need for other stakeholders to complete their own hazard identification and risk assessment for the project (including the development of safe work procedures for specific activities) in due course. | | | | | | |

Identify Hazard				Assess Risk				Implement Risk Treatment					
ID	Risk Source (Hazard)	Event / Cause / Consequence	Persons Affected	Control Measure (Risk Treatment)	Likelihood	Consequence	Risk Rating	Risk Owner	Implement Control - Y/N?	Action / Comment (or justification if no action)	Action Owner(s)	Timing / Date	Status (Open / Closed)
Construction and Commissioning Phase													
1.01	Pipe collapse	Compaction over pipe and/or conduit with insufficient cover causing injury	All construction personnel	Ensure pipe is under pavement boxing area	3 - Likely	D - Significant	Moderate	Contractor	Yes	Locate pipe below boxing area and review conduit material type and class	Designer	Detailed Design Phase	Closed
1.02	Existing underground services	Machinery / construction personnel coming into contact with service, causing injury / death	Contractor	Obtain all known existing services	2 - Unlikely	B - Critical	High	Client	Yes	All known assets shown on drawing. Administrative control considered. Provide warning note on plan, with DBYD reference	Designer	Detailed Design Phase	Closed
1.03	Existing redundant pipes	Potential contamination from reduneted Asbestos water main left by Water Authority.	Contractor	1) Obtain all known existing services. 2) Keep excavation clear from the Asbestos area	3 - Likely	C - Serious	High	Contractor/client	Yes	Add note on drawings to engage a qualified asbestos removelist if encountered. Obtain redundant assets from water authority and incorporate into drawings.	Designer / Contractor	Preliminary Design Phase / Construction	Closed
1.04	Excavation	Excavating near live services causing injury / death	All construction personnel	Dial before you dig information and existing services plans	2 - Unlikely	D - Significant	Low	Contractor	Yes	Consider where practical / applicable	Contractor	Construction Phase	Open
1.05	Unidentified Asbestos	damage to existing services	All construction personnel	1) Obtain all known existing services. 2) Keep excavation clear from the Asbestos area	3 - Likely	C - Serious	High	Contractor/client	Yes	Add note on drawings to engage a qualified asbestos removelist if encountered. Obtain redundant assets from water authority and incorporate into drawings.	Designer / Contractor	Preliminary Design Phase / Construction	Closed
1.06	To steep of a grade to design surfaces	Fall due to to steep of a grade on finished suface causing injury	All construction personnel	Ensure deign is in accordance with suitable grade limits as specified with in the relevant design codes	1 - Very unlikely	D - Significant	Low	Contractor/client	Yes	Ensure deign is in accordance with suitable grade limits as specified with in the relevant design codes	Designer	Detailed Design Phase	Closed
Operations and Maintenance Phase													
2.01	Headwalls	Fall off headwall causing injury	Maintenance / public personnel	Add fencing to headwalls	2 - Unlikely	D - Significant	Low	Client	Yes	Add fencing to headwalls	Designer	Construction Design Phase	Closed
Modification, Demolition and Dismantling Phases													
3.01	Clash with existing services	Damage to existing services causing injury / death	Construction personnel	As-built drawings	1 - Very unlikely	D - Significant	Low	Client	No	Add as-built requirement outside scope of works	Client	Construction Phase	Open
3.02	Excavation	Excavating near live services causing injury / death	Construction personnel	Dial before you dig information and existing services plans	1 - Very unlikely	D - Significant	Low	Client	Yes	Consider where practical / applicable	Contractor	Detailed Design Phase	Open



Plane Tree
Basin

Plot Date: 17/10/2017 3:52:39 PM Office: AUMC Filename: P:250641 MRC0250641 354 MILDURA SOUTH DCP DRAINAGE ASSESSMENT\PROJECT DELIVERY\DRAWINGS\DCU\250641 354\DCG-000 PLANE TREE BASIN.DWG



PLAN
1:500

LEGEND	
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	EXISTING MAJOR CONTOUR
	EXISTING MINOR CONTOUR
	EXISTING PROPERTY PARCEL
	WATER EDGE
	EX-FD EXISTING IRRIGATION DRAINAGE
	EXISTING WATER

PLANE TREE BASIN	
STORAGE VOLUME (WITH 0.300m FREEBOARD)	4997m3
FOOTPRINT AREA	9210m2
AVERAGE DEPTH	1.75m
EXISTING INLET PIPE (P1)	600Ø
EXISTING INLET INVERT (P1)	48.450
EXISTING INLET PIPE (P2)	-
EXISTING INLET INVERT (P2)	49.500
PROPOSED OUTLET PIPE (P3)	375Ø
PROPOSED OUTLET INVERT (P3)	49.500

REV	DATE	REVISION DETAILS	APPROVED
A	02.12.16	PRELIMINARY ISSUE	-


SCALE	SIZE
AS SHOWN	A1
DRAWN	
C.TOTENHOFER	
DESIGNED	
H.SINGH	
CHECKED	

PRELIMINARY NOT FOR CONSTRUCTION
APPROVED
DATE

PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESMENT					
TITLE	PLANE TREE BASIN					
DRAWING No.	PROJECT No.	WBS	TYPE	DISC	NUMBER	REV
	250641	354	DRG	CC	400	A




Calder
Basin




BENETOOK SPURLINE PLAN

1:1000



PIPE (BENETOOK SPURLINE MAIN) LONG SECTION

LEGEND



PIPE SCHEDULE FOR: Benetook Spurline Main

NAME	PIPE INNER Ø [mm]	3D LENGTH	SLOPE	U/S PIT	D/S PIT	U/S INV	D/S INV	PIPE DROP	MATERIAL	COMMENTS
Pipe - 3-1-1	Ø 1067	66.374	1:122	3-1-1	3-2-3	47.745	47.20	0.54	Class 2 RRJ RCP	
Pipe - 3-3-2	Ø 1067	71.118	1:119	3-3-2	3-4-2	46.400	45.80	0.60	Class 2 RRJ RCP	
Pipe - 3-4-2	Ø 1360	61.616	1:77	3-4-2	3-5-3	45.800	45.00	0.80	Class 2 RRJ RCP	
Pipe - 3-5-3	Ø 1360	132.816	1:158	3-5-3	3-6-3	45.000	44.16	0.84	Class 2 RRJ RCP	
Pipe - 3-6-3	Ø 1504	132.694	1:138	3-6-3	3-7-2	44.160	43.20	0.96	Class 2 RRJ RCP	
Pipe - 3-7-2	Ø 1656	73.450	1:367	3-7-2	3-7-2a	43.200	43.00	0.20	Class 2 RRJ RCP	
Pipe - 3-8-1	Ø 1656	57.756	1:340	3-7-2a	3-3-1	43.000	42.83	0.17	Class 2 RRJ RCP	
Pipe - 3-9-1	Ø 1656	15.320	1:511	3-3-1	W3-9-2	42.830	42.80	0.03	Class 2 RRJ RCP	
Pipe - In1	Ø 914	68.195	1:278	Inject 1	In1-a	48.195	47.95	0.24	Class 2 RRJ RCP	
Pipe - In1 (1)	Ø 914	64.540	1:315	In1-a	3-1-1	47.950	47.74	0.21	Class 2 RRJ RCP	
Pipe - 3-2-3	Ø 1067	66.399	1:111	3-2-3	3-3-2	47.000	46.40	0.60	Class 2 RRJ RCP	

PIT SCHEDULE FOR: Benetook Spurline Main

PIT NAME	SETOUT COORDS	INLET INNER Ø [mm]	INLET INV [m]	OUTLET INNER Ø [mm]	OUTLET INV [m]	PIT FIN RL	PIT DEPTH [m]	COMMENTS
3-1-1	E: 606930.355 N: 6213386.391	Ø 914	47.745	Ø 1067	47.745	51.767	4.197	1,500 dia Concrete Manhole
3-2-3	E: 606882.732 N: 6213340.160	Ø 1067	47.200	Ø 1067	47.000	51.689	4.914	2,300 dia Concrete Manhole
3-3-1	E: 606455.255 N: 6212925.094	Ø 1656	42.830	Ø 1656	42.830	46.099	3.362	2,550 dia Concrete Manhole
3-3-2	E: 606835.092 N: 6213293.911	Ø 1067	46.400	Ø 1067	46.400	51.610	5.435	2,050 dia Concrete Manhole
3-4-2	E: 606784.066 N: 6213244.376	Ø 1067	45.800	Ø 1360	45.800	50.628	5.053	2,300 dia Concrete Manhole
3-5-3	E: 606739.859 N: 6213201.461	Ø 1360	45.000	Ø 1360	45.000	49.156	4.381	2,300 dia Concrete Manhole
3-6-3	E: 606644.565 N: 6213108.950	Ø 1360	44.160	Ø 1504	44.160	46.870	2.935	3,000 dia Concrete Manhole
3-7-2	E: 606549.358 N: 6213016.524	Ø 1504	43.200	Ø 1656	43.200	46.405	3.455	3,000 dia Concrete Manhole
3-7-2a	E: 606496.691 N: 6212965.329	Ø 1656	43.000	Ø 1656	43.000	46.296	3.296	2,550 dia Concrete Manhole
In1-a	E: 606976.662 N: 6213431.346	Ø 914	47.950	Ø 914	47.950	51.843	3.893	1,200 dia Concrete Manhole
Inject 1	E: 607025.593 N: 6213478.847			Ø 914	48.195	52.012	3.992	1,200 dia Concrete Manhole
W3-9-2	E: 606439.940 N: 6212925.476	Ø 1656	42.800			44.999		5,800 x 1,890 x 2,350 mm Series 1650 Wingwall


WARNING AND DISCLAIMER BEWARE OF UNDERGROUND SERVICES

The information provided in these drawings relating to the positions of underground services is intended to be only a guide for excavation works. Aurecon does not warrant or represent that the positions of those services shown on the drawings are accurate. Furthermore, services may exist of which Aurecon is unaware. The information provided should therefore not be relied upon and exact positions of services should be verified by hand excavation. Furthermore, Aurecon disclaims responsibility for damage or injury to any person caused directly or indirectly by any works affecting the services.

Dated: May 15



CLIENT



Mildura Rural City Council


REV	DATE	REVISION DETAILS	APPROVED
A	05.08.14	PRELIMINARY	
B	22.08.14	COUNCIL AND LMW COMMENTS INCLUDED	
C	11.09.14	PRELIMINARY ISSUE	
D	14.11.14	PRELIMINARY ISSUE	
E	20.11.14	ISSUED FOR TENDER	
F	11.03.15	ISSUE FOR TENDER	
G	01.05.15	ISSUE FOR TENDER	

SCALE	SIZE
AS SHOWN	A1


DRAWN	DESIGNED	CHECKED
C.TOTENHOFER	M.MCCRANN	

TENDER	APPROVED
NOT FOR CONSTRUCTION	DATE

PROJECT	TITLE	PROJECT No.	WBS	TYPE	DISC	NUMBER	REV
	BENETOOK SPURLINE ADDITIONAL WORKS	240134	306	DRG	CC	0003	G



BENETOOK SPURLINE PLAN
1:1000



LEGEND

	MAJOR DESIGN CONTOUR		EXISTING POWER		PROPOSED HEAD WALL
	MINOR DESIGN CONTOUR		PROPERTY BOUNDARY		DESIGN LEVEL
	EXISTING FENCE		PROPOSED STORM WATER PIPE		DESIGN GRADE
	PROPOSED 1.8m HIGH CYCLONE/WIRE MESH FENCE OR SIMILAR APPROVED		FUTURE STORMWATER PIPE		
	EXISTING STORMWATER		PROPOSED ROCK BEACHING		
	EXISTING SEWER		EXISTING PIT		
	FUTURE SEWER		PROPOSED PIT		
	EXISTING IRRIGATION DRAINAGE				

PIPE SCHEDULE FOR: Benetook Spurline Main

NAME	PIPE INNER Ø [mm]	3D LENGTH	SLOPE	U/S PIT	D/S PIT	U/S INV	D/S INV	PIPE DROP	MATERIAL	COMMENTS
Pipe - 3-1-1	Ø 1067	66.374	1:122	3-1-1	3-2-3	47.745	47.20	0.54	Class 2 RRJ RCP	
Pipe - 3-3-2	Ø 1067	71.118	1:119	3-3-2	3-4-2	46.400	45.80	0.60	Class 2 RRJ RCP	
Pipe - 3-4-2	Ø 1360	61.616	1:77	3-4-2	3-5-3	45.800	45.00	0.80	Class 2 RRJ RCP	
Pipe - 3-5-3	Ø 1360	132.816	1:158	3-5-3	3-6-3	45.000	44.16	0.84	Class 2 RRJ RCP	
Pipe - 3-6-3	Ø 1504	132.694	1:138	3-6-3	3-7-2	44.160	43.20	0.96	Class 2 RRJ RCP	
Pipe - 3-7-2	Ø 1656	73.450	1:367	3-7-2	3-7-2a	43.200	43.00	0.20	Class 2 RRJ RCP	
Pipe - 3-8-1	Ø 1656	57.756	1:340	3-7-2a	3-3-1	43.000	42.83	0.17	Class 2 RRJ RCP	
Pipe - 3-9-1	Ø 1656	15.320	1:511	3-3-1	W3-9-2	42.830	42.80	0.03	Class 2 RRJ RCP	
Pipe - In1	Ø 914	68.195	1:278	Inject 1	In1-a	48.195	47.95	0.24	Class 2 RRJ RCP	
Pipe - In1 (1)	Ø 914	64.540	1:315	In1-a	3-1-1	47.950	47.74	0.21	Class 2 RRJ RCP	
Pipe - 3-2-3	Ø 1067	66.399	1:111	3-2-3	3-3-2	47.000	46.40	0.60	Class 2 RRJ RCP	

PIT SCHEDULE FOR: Benetook Spurline Main

PIT NAME	SETOUT COORDS	INLET INNER Ø [mm]	INLET INV [m]	OUTLET INNER Ø [mm]	OUTLET INV [m]	PIT FIN RL	PIT DEPTH [m]	COMMENTS
3-1-1	E: 606930.355 N: 6213386.391	Ø 914	47.745	Ø 1067	47.745	51.767	4.197	1,500 dia Concrete Manhole
3-2-3	E: 606882.732 N: 6213340.160	Ø 1067	47.200	Ø 1067	47.000	51.689	4.914	2,300 dia Concrete Manhole
3-3-1	E: 606455.255 N: 6212925.094	Ø 1656	42.830	Ø 1656	42.830	46.099	3.362	2,550 dia Concrete Manhole
3-3-2	E: 606835.092 N: 6213293.911	Ø 1067	46.400	Ø 1067	46.400	51.610	5.435	2,050 dia Concrete Manhole
3-4-2	E: 606784.066 N: 6213244.376	Ø 1067	45.800	Ø 1360	45.800	50.628	5.053	2,300 dia Concrete Manhole
3-5-3	E: 606739.859 N: 6213201.461	Ø 1360	45.000	Ø 1360	45.000	49.156	4.381	2,300 dia Concrete Manhole
3-6-3	E: 606644.565 N: 6213108.950	Ø 1360	44.160	Ø 1504	44.160	46.870	2.935	3,000 dia Concrete Manhole
3-7-2	E: 606549.358 N: 6213016.524	Ø 1504	43.200	Ø 1656	43.200	46.405	3.455	3,000 dia Concrete Manhole
3-7-2a	E: 606496.691 N: 6212965.329	Ø 1656	43.000	Ø 1656	43.000	46.296	3.296	2,550 dia Concrete Manhole
In1-a	E: 606976.662 N: 6213431.346	Ø 914	47.950	Ø 914	47.950	51.843	3.893	1,200 dia Concrete Manhole
Inject 1	E: 607025.593 N: 6213478.847			Ø 914	48.195	52.012	3.992	1,200 dia Concrete Manhole
W3-9-2	E: 606439.940 N: 6212925.476	Ø 1656	42.800			44.999		5,800 x 1,890 x 2,350 mm Series 1650 Wingwall

WARNING AND DISCLAIMER BEWARE
OF UNDERGROUND SERVICES


The information provided in these drawings relating to the positions of underground services is intended to be only a guide for excavation works. Aurecon does not warrant or represent that the positions of those services shown on the drawings are accurate. Furthermore, services may exist of which Aurecon is unaware. The information provided should therefore not be relied upon and exact positions of services should be verified by hand excavation. Furthermore, Aurecon disclaims responsibility for damage or injury to any person caused directly or indirectly by any works affecting the services.

Dated: May 15



Plot Date: 23/03/15 12:45:20 PM Client: AUMC Filename: P:\2013\1\BCC\2013\306 BENETOOK SPURLINE ADDITIONAL WORKS\CC\03.DWG

FOR CONTINUATION SEE SHEET C-0004




BENETOOK SPURLINE PLAN
1:1000



LEGEND

- | | | | |
|-----|--|-----|---------------------------|
| --- | FUTURE MAJOR DESIGN CONTOUR | --- | PROPERTY BOUNDARY |
| --- | FUTURE MINOR DESIGN CONTOUR | --- | PROPOSED STORM WATER PIPE |
| --- | EXISTING FENCE | --- | FUTURE STORMWATER PIPE |
| --- | PROPOSED 1.8m HIGH CYCLONE/WIRE MESH FENCE OR SIMILAR APPROVED | --- | PROPOSED ROCK BEACHING |
| --- | EXISTING STORMWATER | --- | EXISTING PIT |
| --- | EXISTING SEWER | --- | PROPOSED PIT |
| --- | FUTURE SEWER | --- | PROPOSED HEAD WALL |
| --- | EXISTING IRRIGATION DRAINAGE | --- | DESIGN LEVEL |
| --- | EXISTING POWER | --- | |



TYPICAL SWALE DETAIL
NOT TO SCALE

**WARNING AND DISCLAIMER BEWARE
OF UNDERGROUND SERVICES**

The information provided in these drawings relating to the positions of underground services is intended to be only a guide for excavation works. Aurecon does not warrant or represent that the positions of those services shown on the drawings are accurate. Furthermore, services may exist of which Aurecon is unaware. The information provided should therefore not be relied upon and exact positions of services should be verified by hand excavation. Furthermore, Aurecon disclaims responsibility for damage or injury to any person caused directly or indirectly by any works affecting the services.

Dated: March 15





REV	DATE	REVISION DETAILS	APPROVED	SCALE	SIZE	TENDER	PROJECT	BENETOOK SPURLINE ADDITIONAL WORKS					
A	05.08.14	PRELIMINARY		AS SHOWN	A1	NOT FOR CONSTRUCTION							
B	22.08.14	COUNCIL AND LMW COMMENTS INCLUDED		DRAWN		APPROVED DATE	TITLE	BENETOOK SPURLINE PLAN & LONGITUDINAL SECTION					
C	11.09.14	PRELIMINARY ISSUE		C.TOTENHOFER									
D	14.11.14	PRELIMINARY ISSUE		DESIGNED									
E	20.11.14	ISSUED FOR TENDER		M.MCCRANN									
F	11.03.15	ISSUE FOR TENDER		CHECKED									



Irymple Basin
- South East

Proj Date: 20/12/2017 8:49:31 AM Office: AUMOL File Name: P:250641 MRC0250641 354 MILDURA SOUTH DCP DRAINAGE ASSESSMENT\PROJECT DELIVERY\CDRAWINGS\CD\250641 354 DRG-500 IRYMPLE BASINS.DWG



- LEGEND**
- PROPOSED MAJOR CONTOUR
 - PROPOSED MINOR CONTOUR
 - EXISTING MAJOR CONTOUR
 - EXISTING MINOR CONTOUR
 - EXISTING PROPERTY PARCEL
 - WATER EDGE
 - EXISTING IRRIGATION DRAINAGE
 - EXISTING WATER
 - EXISTING SEWER

IRYMPLE SOUTH EAST BASIN	
STORAGE VOLUME (WITH 0.300m FREEBOARD)	41520m3
FOOTPRINT AREA	46765m2
AVERAGE DEPTH	1.92m
INLET PIPE (P1)	TBC
INLET INVERT (P1)	TBC
OUTLET PIPE (P1)	900Ø
OUTLET INVERT (P1)	42.500

REV	DATE	REVISION DETAILS	APPROVED
A	11.12.17	PRELIMINARY ISSUE	

SCALE	SIZE
AS SHOWN	A1
DRAWN	
C.TOTENHOFER	
DESIGNED	
H.SINGH	
CHECKED	


PRELIMINARY NOT FOR CONSTRUCTION
APPROVED
DATE

PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESSMENT					
TITLE	IRYMPLE BASIN SOUTH EAST					
DRAWING No.	PROJECT No.	WBS	TYPE	DISC	NUMBER	REV
	250641	354	DRG	CC	500	A




Irymple Basin
- North West

Proj Date: 20/12/2017 8:58:02 AM Office: AUMOL Filename: P:250641-IRCC058641-354-MILDURA SOUTH DCP DRAINAGE ASSESSMENT\PROJECT DELIVERY\CDRAWINGS\CDU\250641-354\DRG-500-IRYMPLE BASINS.DWG



PLAN
1:250



LOCALITY PLAN
NTS

LEGEND

- PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- EXISTING PROPERTY PARCEL
- WATER EDGE
- EXISTING WATER
- EXISTING SEWER

IRYMPLE NORTH WEST	
STORAGE VOLUME (WITH 0.300m FREEBOARD)	15800m3
FOOTPRINT AREA	8800m2
AVERAGE DEPTH	1.80m
INLET PIPE (P1)	900Ø
INLET INVERT (P1)	41.700
OUTLET PIPE (P2)	900Ø
OUTLET INVERT (P2)	41.700

REV	DATE	REVISION DETAILS	APPROVED
A	11.12.17	PRELIMINARY ISSUE	

SCALE AS SHOWN	SIZE A1
DRAWN C.TOTENHOFER	
DESIGNED H.SINGH	
CHECKED	

PRELIMINARY NOT FOR CONSTRUCTION
APPROVED DATE

PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESSMENT
TITLE	IRYMPLE BASIN NORTH WEST
DRAWING No.	PROJECT No. 250641 - WBS 354 - TYPE DRG - DISC CC - NUMBER 400 - REV A



Sandilong Basin
- South East

Proj Date: 20/02/2017 9:09:37 AM Office: AUMOL Filename: P:242814 - MRC242814-38 IRYMPLE DRAINAGE DESIGN\PROJECT DELIVERABLES\STORMWATER\STAGE 5 - SANDILONG BASIN\STAGE 5 - SANDILONG BASIN\STAGE 5 - SANDILONG BASIN\STAGE 5 - SANDILONG BASIN.DWG CC: STS-20000.DWG

Legend

- Ex SW — Ex SW — EXISTING STORMWATER PIPE
- Ex S — Ex S — EXISTING SEWER
- GAS — GAS — EXISTING GAS
- E-UG — E-UG — EXISTING ELECTRICAL CONDUIT
- OH — OH — EXISTING OVERHEAD POWER
- TELSTRA — TELSTRA — EXISTING TELSTRA
- TFO — TFO — EXISTING TELSTRA FIBRE-OPTIC LINE
- Ex FO — Ex FO — EXISTING NEXTGEN FIBRE-OPTIC LINE
- EX-W — EX-W — EXISTING LMW WATER MAIN - HYDRANTS & VALVES
- RET-W — RET-W — RETIRED LMW WATER MAIN
- EX-WI — EX-WI — EXISTING LMW IRRIGATION WATER MAIN
- EX-FD — EX-FD — EXISTING LMW IRRIGATION DRAINAGE MAIN

SANDILONG BASIN - NORTH WEST


STORAGE VOLUME	6000m3
FOOTPRINT AREA	4283m2
AVERAGE DEPTH	1.4m
INLET PIPE (P1)	12000
INLET INVERT (P1)	46.474
OUTLET PIPE (P2)	5250
OUTLET INVERT (P2)	46.20

SANDILONG BASIN - SOUTH EAST

STORAGE VOLUME	15000m3
FOOTPRINT AREA	10500m2
AVERAGE DEPTH	1.43m
INLET PIPE (P1)	2 x 9000
INLET INVERT (P1)	43.527
OUTLET PIPE (P2)	6750
OUTLET INVERT (P2)	43.194



www.aurecongroup.com



Mildura Rural City Council



CLIENT				SCALE		SIZE		PROJECT	
REV	DATE	REVISION DETAILS		APPROVED		1:750		A1	
A	13.05.16	PRELIMINARY ISSUE						IRYMPLE DRAINAGE	
								SANDILONG BASINS	
								SOUTH EAST & NORTH WEST	
								TITLE	
								DRAWING No.	
								PROJECT No.	
								WBS	
								TYPE	
								DISC	
								NUMBER	
								REV	
								A	



Sandilong Basin - North West



 Mildura Rural City Council	CLIENT	REV	DATE	REVISION DETAILS	APPROVED	SCALE	SIZE	PRELIMINARY NOT FOR CONSTRUCTION	PROJECT
		A	13.05.16	PRELIMINARY ISSUE		AS SHOWN	A1		IRYMPLE DRAINAGE
						DRAWN		APPROVED DATE	TITLE
						M.PENDLEBURY			SANDILONG BASIN
						DESIGNED			
						H.SINGH			
						CHECKED			
									DRAWING No. PROJECT No. 242814 - WBS 328 - TYPE DRG - DISC CC - NUMBER 100 - REV A



 Mildura Rural City Council	CLIENT	REV	DATE	REVISION DETAILS	APPROVED	SCALE	SIZE	PRELIMINARY NOT FOR CONSTRUCTION	PROJECT	IRYMPLE DRAINAGE										
		A	13.05.16	PRELIMINARY ISSUE		AS SHOWN	A1			TITLE	SANDILONG BASIN									
						DRAWN M.PENDLEBURY				APPROVED DATE										
						DESIGNED H.SINGH														
						CHECKED														
									DRAWING No.	PROJECT No.	WBS	TYPE	DISC	NUMBER	REV					
										242814	-	328	-	DRG	-	CC	-	101	-	A

Legend

- EX-WP EX-WP EXISTING STORMWATER PIPE
- EX-S EX-S EXISTING SEWER
- e GAS EXISTING GAS
- E-UG E-UG EXISTING ELECTRICAL CONDUIT
- e OH EXISTING OVERHEAD POWER
- TELSTRA EXISTING TELSTRA
- TFO TFO EXISTING TELSTRA FIBRE-OPTIC LINE
- EX-FO EX-FO EXISTING NEXTGEN FIBRE-OPTIC LINE
- EX-W EX-W EXISTING LMW WATER MAIN - HYDRANTS & VALVES
- RET-W RET-W RETIRED LMW WATER MAIN
- EX-WI EX-WI EXISTING LMW IRRIGATION WATER MAIN
- EX-PD EX-PD EXISTING LMW IRRIGATION DRAINAGE MAIN



Proj Date: 27/03/2017 12:52:41 PM Client: AURECON Filename: P:\202814 - MRC\242814\38 IRYMPLE DRAINAGE DESIGN\PROJECT DELIVERABLES\DESIGN\STORMWATER\STAGE 5 - SANDILONG BASIN\STAGE 5 - SANDILONG BASIN.DWG CC: STS-2000.DWG

REV	DATE	REVISION DETAILS	APPROVED
A	13.05.16	PRELIMINARY ISSUE	

SCALE	SIZE
AS SHOWN	A1
DRAWN	
M.PENDLEBURY	
DESIGNED	
H.SINGH	
CHECKED	

PRELIMINARY NOT FOR CONSTRUCTION
APPROVED
DATE

PROJECT	IRYMPLE DRAINAGE				
TITLE	SANDILONG BASIN				
DRAWING No.	PROJECT No.	WBS	TYPE	DISC	NUMBER
242814	-	328	-	DRG	CC
					102
					REV
					A

Plot Date: 27/03/2017 12:53:07 PM Office: AUMC Filename: P1202814_IRMCC242814381RYMPLE DRAINAGE DESIGN\PROJECT DELIVERABLES\STORMWATER\STAGE 5- SANDILONG BASIN\STAGE 5- SANDILONG BASIN\STAGE 5- SANDILONG BASIN.DWG CC-ST5-2000.DWG

Legend

Ex SW

Ex S

e

ExUG

e

e

TELSTRA

TFO

ExFO

Ex-W

Ex-W

Ex-W

Ex-FD

EXISTING STORMWATER PIPE

EXISTING SEWER

EXISTING GAS

EXISTING ELECTRICAL CONDUIT

EXISTING OVERHEAD POWER

EXISTING TELSTRA

EXISTING TELSTRA FIBRE-OPTIC LINE


EXISTING NEXTGEN FIBRE-OPTIC LINE

EXISTING LMW WATER MAIN - HYDRANTS & VALVES

RETIRED LMW WATER MAIN

EXISTING LMW IRRIGATION WATER MAIN

EXISTING LMW IRRIGATION DRAINAGE MAIN




REV	DATE	REVISION DETAILS	APPROVED
A	13.05.16	PRELIMINARY ISSUE	

SCALE	SIZE
AS SHOWN	A1
DRAWN	
M.PENDLEBURY	
DESIGNED	
H.SINGH	
CHECKED	

PRELIMINARY NOT FOR CONSTRUCTION
APPROVED
DATE


PROJECT	IRYMPLE DRAINAGE	
TITLE	SANDILONG BASIN	
DRAWING No.	242814	
PROJECT No.	242814	
WBS	328	
TYPE	DRG	
DISC	CC	
NUMBER	103	
REV	A	



SCALE: H 1:250 1:50
Datum 45.000

GRADE %	0.45%	0.25%	0.50%	-0.50%	0.50%	0.50%	0.50%	0.50%
PIPE DETAILS (CL to CL LENGTHS)	1,219 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 72.475m	1,219 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 200.865m	1,219 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 39.732m	1,219 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 100.093m	1,067 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 90.723m	1,067 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 100.001m	838 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 99.979m	686 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 140.031m
DESIGN LEVEL AT MH CL	46.065	49.815	50.379	50.208	50.038	50.182	50.660	51.531
INVERT LEVEL	46.320	46.647 46.650	47.151 47.151	47.350 47.349	47.850 47.850	48.304 48.303	48.803 48.802	49.303 49.303
COVER	1.056	1.872 1.870	1.932 1.933	1.563 1.564	0.893 1.045	0.737 0.737	0.713 0.965	1.637 1.795
CHAINAGE	1.999	74.473	275.947	315.079	415.170	505.892	605.892	705.870


ALIGN1-R02 LONG SECTION



SCALE: H 1:250 1:50
Datum 35.000

GRADE %	1.33%	1.00%	1.00%	1.00%	0.20%	1.30%
PIPE DETAILS (CL to CL LENGTHS)	914 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 30.843m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 47.929m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 30.347m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 100.042m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 164.992m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 21.641m
DESIGN LEVEL AT MH CL	44.955	45.935	46.743	47.103	49.400	48.957
INVERT LEVEL	43.527	43.804 43.804	44.263 44.266	44.590 44.587	45.589 45.588	45.918 45.918
COVER	1.219	1.153 1.153	1.482 1.382	2.019 2.021	3.316 3.317	2.546 2.546
CHAINAGE	0.000	20.842	68.768	99.114	199.150	364.142

ALIGN2-R03 LONG SECTION



SCALE: H 1:250 1:50
Datum 35.000

GRADE %	0.37%	0.38%
PIPE DETAILS (CL to CL LENGTHS)	686 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 64.203m	686 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 98.735m
DESIGN LEVEL AT MH CL	43.773	44.326
INVERT LEVEL	42.569	42.828 42.828
COVER	-0.391	0.764 0.764
CHAINAGE	0.000	64.203

ALIGN3-R07 LONG SECTION



SCALE: H 1:250 1:50
Datum 35.000

GRADE %	-0.76%	-0.76%	-0.75%	-0.76%
PIPE DETAILS (CL to CL LENGTHS)	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 27.746m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 42.776m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 100.003m	457 mm Concrete Pipe ANZ CONCRETE PIPE RCRRJ 100.003m
DESIGN LEVEL AT MH CL	44.139	45.163	45.266	45.744
INVERT LEVEL	43.194	43.404 43.404	43.727 43.727	44.482 44.482
COVER	1.584	1.265 1.265	1.044 1.044	0.767 0.767
CHAINAGE	0.000	27.746	777	170.520

ALIGN4-R08 LONG SECTION

Proj Date: 27/03/2017 3:04:01 PM Client: AUMC File Name: P:\202814 - IRYMPLE DRAINAGE DESIGN\PROJECT DELIVERABLES\STATION WATER STAGE 5 - SANDHOLONG BASIN\STAGE 5 - SANDHOLONG BASIN\4.3B-DWG-CC-ST5-0000.DWG

REV	DATE	REVISION DETAILS	APPROVED
A	13.05.16	PRELIMINARY ISSUE	


SCALE	SIZE
AS SHOWN	A1
DRAWN	
M.PENDLEBURY	
DESIGNED	
H.SINGH	
CHECKED	

PRELIMINARY NOT FOR CONSTRUCTION
APPROVED
DATE

PROJECT	IRYMPLE DRAINAGE
TITLE	PIPE LONG SECTIONS
DRAWING No.	242814
PROJECT No.	
WBS	328
TYPE	DRG
DISC	CC
NUMBER	200
REV	A



Henderson
Basin



LEGEND	
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	EXISTING MAJOR CONTOUR
	EXISTING MINOR CONTOUR
	EXISTING PROPERTY PARCEL
	WATER EDGE
	EXISTING STORM WATER

HENDERSON BASIN	
STORAGE VOLUME (WITH 0.300m FREEBOARD)	30305m3
FOOTPRINT AREA	14932m2
AVERAGE DEPTH	3.5m
INLET PIPE (P1)	22500
INLET INVERT (P1)	42.280
OUTLET PIPE (P1)	12000
OUTLET INVERT (P1)	42.280

PLAN
1:500

File Path: 17/10/2017 14:53 PM User: JMM File Name: P250641 MDC250641 SA MILDURA SOUTH DCP DRAINAGE ASSESSMENT 13 PROJECT DELIVERY CAD DRAWINGS\250641.DWG Project: 200 HENDERSON BASIN.DWG

REV	DATE	REVISION DETAILS	APPROVED	SCALE	SIZE	PRELIMINARY NOT FOR CONSTRUCTION	PROJECT	MILDURA SOUTH DCP DRAINAGE ASSESSMENT						
A	07.12.16	PRELIMINARY ISSUE	-	AS SHOWN	A1	APPROVED DATE	TITLE	HENDERSON BASIN						
				DRAWN C.TOTENHOFFER	DRAWING No.			PROJECT No.	WBS	TYPE	DISC	NUMBER	REV	
				DESIGNED H.SINGH										
				CHECKED										